

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19549-00-00
Spot: NWNWNWNW Sec/Twnshp/Rge: 29-25S-5E
5106 feet from S Section Line, 5116 feet from E Section Line
Lease Name: FINNEY 1 Well #: 29
County: BUTLER Total Vertical Depth: 720 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	666		60 SX
SURF	10.5	43		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/10/2016 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/10/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 660', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS CLASS A COMMON 4% GEL 3% CC 100# HULLS TO SURFACE, PULLED TBG @ 270', CIRCULATED HOLE CLEAN. TAGGED CEMENT @ 301', LOADED HOLE & PRESSURED CASING @ 300#, HELD OK. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 250'-251' (4 HOLES). RIH W/TBG @ 270', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 45 SXS 60/40 POZMIX 4% GEL, 2% CC. 1/4# FLOW-SEAL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM., 11-10-2016. CONSOLIDATED OILWELL SERVICES TICKET #51447.

Perfs:

Top	Bot	Thru	Comments
682	720	OH	

Remarks: BACKSIDE CEMENT @ SURFACE / 10 YEAR RULE

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

Form CP-2/3

1/4
DEC 21 2016