

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-193-20483-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 8-10S-33W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: REIGER Well #: 1-8
County: THOMAS Total Vertical Depth: 4800 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4764		250 SX
SURF	8.625	320		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/17/2016 11:00 AM
Plug Co. License No.: 32938 Plug Co. Name: NORTH FORK WELL SERVICE LLC
Proposal Rcvd. from: DYLAN KLAUS Company: VESS OIL CORP DBA Phone: (316) 682-1537

Proposed 8 5/8 surface casing set @ 320' W/200' sx.
Plugging 4 1/2 production casing set @ 4764' W/250' sx.
Method: Port Collar set @ 2682' W/550' sx.
Perforations: 4611-16', 4583-91' & 4363-69'.
TD 4800', PBTD 4587'.
CIBP's removed.

Plugging Proposal Received By: CASE MORRIS WitnessType: PARTIAL
Date/Time Plugging Completed: 11/17/2016 2:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4330' and pumped 100 sx cement mixed with 300 # hulls.
Pulled tubing to 3060' and pumped 100 sx cement mixed with 150 # hulls.
Pulled tubing to 1500' and pumped 100 sx cement mixed with 100 # hulls. Cement circulated to surface.
Pulled tubing to surface.
Connected to 8 5/8 surface casing. Pumped 20 sx cement and pressured to 300 psi.
Connected to 4 1/2 production casing and pumped 20 sx cement.

GPS -101.03608W & 39.19731N.

Perfs:

Top	Bot	Thru	Comments
4611	4616		
4583	4591		
4363	4369		

Remarks: NORTH FORK WELL SERVICE LLC RIG AND BASIC ENERGY SERVICES LP. CEMENT TICKET # 14,149.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

KCC WICHITA

(TECHNICIAN)

CM

NOV 29 2016

RECEIVED

Form CP-2/3

NOV 21 2016

DEC 21 2016