

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-109-20373-00-00  
Spot: NWSE Sec/Twnshp/Rge: 15-13S-33W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: S S S SMOKY VALLEY Well #: 1  
County: LOGAN Total Vertical Depth: 4610 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4604		225 SX
SURF	8.625	748		425 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/18/2016 11:00 AM  
Plug Co. License No.: 32938 Plug Co. Name: NORTH FORK WELL SERVICE LLC  
Proposal Rcvd. from: DAVID VAN DYKE Company: VESS OIL CORPORATION DBA Phone: (316) 682-1537

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/650 # hulls.  
8 5/8 surface casing set @ 748' W/425 sx.  
4 1/2 production casing set @ 4604' W/225' sx.  
TD 4610'. PBD 4551'  
DV tool set @ 1676'  
Perforations: 4473-83', 4096-4100', 4066-68' & 3973-76'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/18/2016 2:45 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 3950' and pumped 100 sx cement with 350 # hulls.  
Pulled tubing to 2950' and pumped 100 sx cement with 200 # hulls.  
Pulled tubing to 1475' and pumped 175 sx cement mixed with 100 # hulls. Cement circulated to surface.  
Pulled tubing to surface.  
Connected to 4 1/2 production casing and pumped 25 sx cement.  
Connected to 8 5/8 surface casing and pumped 50 sx cement. Pressured to 100 psi.  
GPS -100.97002W & 38.92155N.

Perfs:

Top	Bot	Thru	Comments
4473	4483		
4096	4100		
4066	4068		
3973	3976		

Remarks: NORTH FORK WELL SERVICE LLC SERVICE UNIT & BASIC ENERGY SERVICES LP. CEMENT TICKET # 14,150.

Plugged through: TBG

District: 04

Signed

*Darrel Dipman*

(TECHNICIAN)

CM

KCC WICHITA

NOV 29 2016

RECEIVED

NOV 21 2016

DEC 21 2016

Form CP-2/3