

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-23161-00-02  
Spot: SEWNNE Sec/Twnshp/Rge: 16-28S-4E  
4045 feet from S Section Line, 1386 feet from E Section Line  
Lease Name: BROWN A Well #: 24  
County: BUTLER Total Vertical Depth: 2676 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2500		
PROD	5.5	2675		200 SX
SURF	8.625	265		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/16/2016 8:00 AM  
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.  
Proposal Revd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/16/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2450', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS CLASS A COMMON 4% GEL 3% CC 100# HULLS & DISPLACED IN CASING. TAGGED CEMENT @ 1881'. LOADED HOLE & PRESSURED CASING @ 250#, HELD OK. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @ 300'-301'. SWEDGED INTO CASING, CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 115 SXS 60/40 POZMIX 4% GEL, 2% CC, TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 P.M. 11-16-2016. CONSOLIDATED OILWELL SERVICES TICKET #51449.

Perfs:

Top	Bot	Thru	Comments
2507	2514	CSG	
2469	2474	CSG	

Remarks: 10 YEAR RULE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER  
(TECHNICIAN)

BCW  
DEC 21 2016