

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-21809-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 7-16S-30W
999 feet from S Section Line, 2096 feet from E Section Line
Lease Name: YORK A Well #: 1
County: LANE Total Vertical Depth: 4479 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		2153		WITH 300 SX CMT
PROD	4.5	3963	0	WITH 125 SX CMT
SURF	8.625	265		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2016 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: JOE RUPP Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: PUMP 35 SX CMT WITH 100# HULLS. TBG TO 2180' & CIRCULATE CMT TO 0'. TOP OFF & PRESSURE BACKSIDE TO 500# WITH CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2016 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

TBG PARTED & LEFT 19 JOINTS OF TBG OR PACKER IN WELL. TOP OF FISH AT 3300'. SPOT 50 SX CMT WITH 300# HULLS AT 3300'. FULL CIRCULATION. CIRCULATE CMT FROM 2205' TO 0' WITH 135 SX CMT. TOP OFF WITH 20 SX CMT. 5 SX CMT DOWN THE ANNULUS TO 500#.

Top	Bot	Thru	Comments
3834	3844		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
5/18

(TECHNICIAN)

RECEIVED
NOV 17 2016
KCC DODGE CITY

MR

ACW
DEC 21 2016

Form CP-2/3