

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-23443-00-00  
Spot: SEWSE Sec/Twnshp/Rge: 18-7S-20W  
1890 feet from S Section Line, 1430 feet from E Section Line  
Lease Name: IDA MAE Well #: 1  
County: ROOKS Total Vertical Depth: 3630 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: PO BOX 723  
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3628		150 SX
SURF	8.625	208		150 SX
T1	2.375	3610		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/02/2016 10:00 AM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement.  
Well was cemented back to 2135' w/150 sx cement on 11/13/2006.  
Production perforations: 3344' - 3415' LKC

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/02/2016 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2135' and pumped 100 sx cement. Pulled tubing to 1158' and pumped 75 sx cement to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing with 15 sx cement. Hooked to 8 5/8' x 5 1/2' annulus and pressured immediately to 300 psi.

GPS: 39.44279N -099.58945W

Perfs:

Top	Bot	Thru	Comments
3411	3415		
3371	3375		
3344	3415		

KCC WICHITA  
DEC 19 2016  
RECEIVED

Remarks: GLOBAL CEMENTING TICKET # 2776

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

DEC 05 2016

DEC 21 2016

Form CP-2/3