

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-147-20717-00-00
Spot: SWSWNSW Sec/Twnshp/Rge: 10-1S-19W
1585 feet from S Section Line, 1400 feet from W Section Line
Lease Name: KATS UNIT Well #: 1
County: PHILLIPS Total Vertical Depth: 3630 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3630		600 SX
SURF	8.625	222		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/23/2016 1:00 PM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed Plugging Method: Orderd 295 sx 60/40 pozmix 4% gel cement, 1200 # gel (12 sx gel) and 400 # hulls.
Production perforations: 3401' - 3563'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/23/2016 2:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2' casing and pumped 50 sx cement w/200 # hulls followed by 12 sx gel, followed by 140 sx cement w/200 # hulls. Shut in pressure 500 psi. Hooked to 8 5/8" x 5 1/2" annulus and pumped 1/4 bbl. Shut in pressure 500 psi.

GPS: 39.97752N -099.45462W

Perfs:

Top	Bot	Thru	Comments
3561	3563		
3520	3530		
3419	3424		
3401	3563		

KCC WICHITA
DEC 19 2016
RECEIVED

Remarks: GLOBAL CEMENTING TICKET # 2783

Plugged through: CSG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

DEC 05 2016

DEC 21 2016

Form CP-2/3