

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-147-20746-00-00  
Spot: SWNESENE Sec/Twnshp/Rge: 3-1S-19W  
3362 feet from S Section Line, 360 feet from E Section Line  
Lease Name: COX Well #: 1  
County: PHILLIPS Total Vertical Depth: 3438 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: PO BOX 723  
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3541		600 SX
SURF	8.625	220		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/23/2016 11:00 AM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed Plugging Method: Ordered 285 sx 60/40 pozmix 4% gel cement w/1200 # gel (12 sx gel) and 400 # hulls.  
Production perforations: 3302' - 3428'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/23/2016 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 50 sx cement w/200 # hulls, followed by 12 sx gel, followed by 225 sx cement w/200 # hulls. Hooked to 8 5/8" x 5 1/2" annulus and pumped 1/2 bbl. Shut in pressure 500 psi.  
GPS: 39.99677N -099.44225W

Perfs:

Top	Bot	Thru	Comments
3420	3428		
3302	3428		

KCC WICHITA  
DEC 19 2016  
RECEIVED

Remarks: GLOBAL CEMENTING TICKET # 2782  
Plugged through: CSG

District: 04 Signed Pat Bedore  
(TECHNICIAN) *CM*

DEC 05 2016

DEC 21 2016