

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-21937-00-01  
Spot: SENWNW Sec/Twnshp/Rge: 36-15S-19W  
4233 feet from S Section Line, 4344 feet from E Section Line  
Lease Name: BRAUN Well #: 3  
County: ELLIS Total Vertical Depth: 3714 feet

Operator License No.: 33922  
Op Name: MUSTANG ENERGY CORPORATION  
Address: PO BOX 1121  
HAYS, KS 67601

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 5.5   | 3689       |             | 125 SX   |
| SURF   | 8.625 | 1150       |             | 150 SX   |

Well Type: SWD UIC Docket No: D23001.0 Date/Time to Plug: 11/10/2016 9:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: ROD BRIN Company: MUSTANG ENERGY CORP. Phone: (785) 623-0533

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 12 sx gel and 700 # hulls.  
Peforations: 3689' - 3729'.  
Alt-I completion.  
Squeezed from 2707' - 2765' w/150 sx cement, 2424' - 2486' w/200 sx cement, 2656' - 2846' w/150 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/10/2016 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Outlaw ran in hole with tubing to 3680' and pumped 75 sx cement w/300 # hulls. Pulled tubing to 3036' and pumped 12 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1259' and pumped 150 sx cement w/200 # hulls to circulate cement up 5 1/2" casing. Pulled tubing. Topped off 5 1/2" casing with 15 sx cement. Hole standing full. Rigged to 8 5/8" surface casing with instant pressure.

GPS: 38.70848 -099.39098

Perfs:

Remarks: QUALITY OILWELL CEMENTING TICKET # 3102

Plugged through: TBG

District: 04

Signed

  
(TECHNICIAN)

CM

KCC WICHITA

NOV 29 2016

RECEIVED

NOV 14 2016

DEC 21 2016 Form CP-2/3