

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-22523-00-01  
Spot: NWNWSWNW Sec/Twnshp/Rge: 21-33S-12E  
3658 feet from S Section Line, 4987 feet from E Section Line  
Lease Name: FOLTZ Well #: W 1  
County: CHAUTAUQUA Total Vertical Depth: 713 feet

Operator License No.: 32255  
Op Name: KANSAS ENERGY COMPANY, L.L.C.  
Address: BOX 68  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	713		90 SX
SURF	7	90		20 SX

Well Type: SWD UIC Docket No: D20940.0 Date/Time to Plug: 10/25/2016 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: P.J. BUCK Company: Phone: (620) 725-3636

Proposed Plugging Method: Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/26/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 700' circulated cement to surface. Pulled 1" and topped well off. Hooked onto casing and squeezed cement down casing. Shut in with 800 psi on casing. A total of 22 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
640	660		
RECEIVED KCC DIST # 3 DEC 13 2016 CHANUTE, KS  <i>DS</i>			

Remarks: WE;LL WAS PLUGGED DUE PLUGGING AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed *[Signature]*  
(TECHNICIAN) *pm*

KCC WICHITA  
DEC 16 2016  
RECEIVED

DEC 21 2016 Form CP-2/3