

1 070731

10-4

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,606-0000
SE SE SE, SEC. 15, T 22 S, R 11 W/E

TECHNICIAN'S PLUGGING REPORT

330 feet from S section line
330 feet from E section line

Operator License # 5015

Lease Name Shepard Heter Well #1

Operator: Hellar Drilling Company, Inc.
Name &
Address 125 North Market, Suite 1422
Wichita, KS 67202

County Stafford 118.43

Well Total Depth 3644 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 2:30 a.m. Day: 4 Month: 10 Year: 19 89

Plugging proposal received from Bill Craig

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1780'
Anhydrite 485-91'

1st plug at 3600' with 40 sx cement, 2nd plug at 500' with 40 sx cement,

3rd plug at 280' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:30 a.m. Day: 4 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 3600' with 40 sx cement,

2nd plug at 500' with 40 sx cement,

3rd plug at 280' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

Water well plugged with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO.

(If additional description is necessary, use BACK of this form.)

INVOICED

(X) (did not) observe this plugging.

DATE 10-11-89

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 26085

10-4

RECEIVED
STATE CORPORATION COMMISSION
OCT 08 1989
10-6-89
CONSERVATION DIVISION
Wichita, Kansas

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date 9 18 89
month day year

SE SE SE... Sec 15. Twp 22 S, Rg 11. East West

OPERATOR: License # 5015
Name: Hellar Drilling Co., Inc.
Address: 125 N. Market Suite 1422
City/State/Zip: Wichita, Ks. 67202
Contact Person: Don Hellar
Phone: 316-267-2845

330 feet from South line of Section
330 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 5422
Name: Abercrombie Drilling, Inc.

County: Stafford
Lease Name: Shepard Heter Well # 1
Field Name: Unknown

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWD ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes X no
Target Formation(s): Arbuckle
Nearest lease or unit boundary: 330
Ground Surface Elevation: 1780 GL feet MSL
Domestic well within 330 feet: ... yes X no
Municipal well within one mile: ... yes X no
Depth to bottom of fresh water: 100
Depth to bottom of usable water: 200
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 250
Length of Conductor pipe required: None
Projected Total Depth: 3700
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
X well ... farm pond ... other
DWR Permit #: Unknown
Will Cores Be Taken?: ... yes X ... no
If yes, proposed zone: N/A

If OAWD: old well information as follows:
Operator: N/A
Well Name: N/A
Comp. Date: Old Total Depth


Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, total depth location: Exp. 3/8/90

220' Alt. I Req.

AFFIDAVIT

PUSHER Bill Coaig
TD 3644 FORMATION Arb.
SURFACE PIPE 8 5/8" @ 261'
ANHYDRITE 485' ELEVATION 1780'
STARTING TIME & DATE 2:30 pm 10-4
COMPLETION TIME & DATE 7:30
1st PLUG @ 3600 FT. W/ 40 SX
2nd PLUG @ 500 FT. W/ 40 SX
3rd PLUG @ 280 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 15 SX
WATER WELL PLUGGED W/ 15 SX
CEMENT COMPANY Howco
TECHNICIAN D.G.

Spud 9-24-89
250' @ 8 5/8"
has water well
RECEIVED
STATE CORPORATION COMMISSION
OCT 06 1989
CONSERVATION DIVISION
Wichita, Kansas



6 months of effective date.
Spud date: _____ Agent: _____

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
 - File Completion Form ACD-1 within 120 days of spud date;
 - File acreage attribution plat according to field proration orders;
 - Notify appropriate district office 48 hours prior to workover or re-entry;
 - Submit plugging report (CP-4) after plugging is completed;
 - Obtain written approval before disposing or injecting salt water.