

1090531 3-30

API NUMBER 15- 083-20,185-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

App. C SW NE, SEC. 6, T 22 S, R 24 WKE

3400 feet from S section line

1930 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3122

Lease Name Schauvliege B Well # 2

Operator: Vintage Petroleum, Inc.

County Hodgeman

Name & Address 4200 One Williams Center

Well Total Depth 4670 151.78 feet

Tulsa, OK 74172

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 600

Abandoned Oil Well  Gas Well  Input Well  SMD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address P.O. Box 428, Hays, KS 67601

Company to plug at: Hour: 10:15 a.m. Day: 30 Month: 3 Year: 19 95

Plugging proposal received from Neil Pfannenstiel

(company name) Vintage Petroleum, Inc. (phone) 913-798-2850

work: 4 1/2" at 4669' w/125 sx cement, EBTD 4626', Perfs at 4577-84', Squeezed at 1130' w/250  
1st plug pump down 4 1/2" casing with 2 sx hulls and cement to surface. sx cement

Check backside.

4-5-95

STATE RECEIVED CORPORATION COMMISSION

APR - 5 1995

Plugging Proposal Received by Steve Middleton

CONSERVATION DIVISION (TECHNICIAN) KANSAS

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11 a.m. Day: 30 Month: 3 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 5 sx hulls and 323 sx cement.  
Maximum pressure 800 psi and shut in 500 psi.

2nd plug hooked onto backside and pumped in 100 sx cement. Maximum pressure 400 psi and  
shut in 150 psi.

Remarks: Used 65/35 Pozmix 8% gel by Halliburton. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED (VOID) observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 4-10-95

INV. NO. 42554

