

To: 1 090535 4-6  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION App.  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 083-20,198-0000  
C SE NE, SEC. 6, T 22 S, R 24 W/E  
1890 feet from ~~N~~ section line  
760 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3122

Lease Name Schauvliege B Well # 3

Operator: Vintage Petroleum, Inc.

County Hodgeman

Name & Address 4200 One Williams Center

Well Total Depth 4625 150.31 feet

Tulsa, OK 74172

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 590

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton License Number \_\_\_\_\_

Address P.O. Box 428, Hays, KS 67601

Company to plug at: Hour: 1 p.m. Day: 6 Month: 4 Year: 19 95

Plugging proposal received from Neil Pfannenstiel

(company name) Vintage Petroleum (phone) 913-798-2850

were: 4 1/2" at 4624' w/124 sx cement, Perfs at 4546-53'

1st plug run tubing to 4550' and spot 25 sx cement and 2 1/2 sx hulls on top, 4-10-95

2nd plug run gel to 890' and perforate at 800', circulate cement to surface through tubing,

3rd plug pull tubing out and pump 80 sx cement down casing.

Check backside.

Plugging Proposal Received by Steve Middleton

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:35 p.m. Day: 6 Month: 4 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug ran tubing to 4500' and spotted 2 1/2 sx hulls and 25 sx cement,

2nd plug gel to 890', perforated casing at 850' and circulated 67. sx cement to surface,

3rd plug pulled tubing out of hole, hooked on to 4 1/2" casing, and pumped 60 sx cement.

Maximum pressure 400 psi and shut in 50 psi.

4th plug hooked on to backside and pumped in 200 sx cement. Maximum pressure 900 psi and

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery. shut in 50 psi.

(if additional description is necessary, use BACK of this form.)

**INVOICED** (if applicable) observe this plugging.

DATE 4-13-95

INV. NO. 42574

Signed [Signature] (TECHNICIAN)

4-6 JUN 21 1995