

To: 1030646  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 083-20,341-0000

C SE NW, SEC. 4, T 22 S, R 24 W/E  
3300 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5258

Lease Name WCTU Well # 2

Operator: Dane G. Hansen Trust  
Name & Address P. O. Box 187  
Logan, KS 67646

County Hodgeman 151.13  
Well Total Depth 4650 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 14 Month: January Year: 19 86

Plugging proposal received from Dan Kilgore

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4640' Open Hole

1st plug sand back to 4600' and dump 5 sx cement

1-27-86

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Plugging Proposal Received by Robert B. Tarbutton

JAN 27 1986

(TECHNICIAN) CONSERVATION DIVISION

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:00 pm Day: 15 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4600' and dumped 5 sx cement on top of

sand through bailer, 2nd plug pumped 3 sx hulls, 15 sx gel, and 30 sx cement. Cement

outside surface pipe. 1-15-86 1st plug pumped 10 sx gel and 50 sx cement at

Pumped plugs through tubing with mud between plugs

1050', 2nd plug at 650' with 50 sx cement, 3rd plug at 270' with 40 sx cement, 4th

& 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

**INVOICED**

(If desired, you may wish to observe this plugging.)

DATE JAN 30 1986

Signed Steve Quenert  
(TECHNICIAN)

INV. NO. 12173