

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-159-21074-0000

SWSW, Sec. 3, T 22 S, R 8 W/E

feet from N/S section line

feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5290

Lease Name Mayer "A" Well # 1

Operator: Hinkle Oil Company
Name & Address 1016 Union Center
Wichita, Kansas 67202

County Rice

Well Total Depth 3480 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 238'-200 sacks

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, Kansas KCC Rig # 548

Company to plug at: Hour: 9:00 AM Day: 19 Month: October Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Norman Voth

(company name) Kelso Casing Pulling (phone) 916-938-2457

were: Squeeze bottom w/50 sacks pumped to 3000' or lower in 4 1/2" casing. Squeeze hole with 5 sacks hulls, 25 sacks gel, and 100 sacks 50/50 Pozmix w/2% gel and 3% C.C. (Pump into 8 5/8" surface casing)

Signed [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:00 AM Day: 19 Month: October Year: 1982

ACTUAL PLUGGING REPORT Bottom squeezed w/50 sacks cement pumped into 4 1/2" casing (Top @ 3300') Hole squeezed with 5 sacks hulls, 25 sacks gel-mud, and 100 sacks 50/50 Pozmix w/2% gel and 3% c.c. Pumped into 8 5/8" surface casing.

RECEIVED STATE CORPORATION COMMISSION

Remarks: 2835' of 4 1/2" casing recovered. Cementing Contractor: Sun Oilwell Cementing

OCT 26 1982

CONSERVATION DIVISION Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICE

DATE 11-5-82

INV. NO. 1487-CW

Signed [Signature] (TECHNICIAN)

