

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 69-1LOCATION NW SW SWSEC. 2 TWP. 14 RGE. 15Dry Hole Abandoned Oil Well x Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. A-5 Lease CrawfordOperator Cities Service Co Address Great BendField Gorham County RussellTotal Depth 3286 Feet.

(Describe briefly the manner in which the well was plugged)

12½" at 919' with 50 sax cement behind and mudded to surface-
7" at 3283'.

String cable tools lost in bottom hole, dumped 5 sax cement
on top tools to 3200' - pulled 2915' of 7", filled hole with heavy
mud to 210', let set 24 hours, set bridge and 34 sax cement,
filled hole with heavy mud to 30', set rock bridge and 15 sax
cement to bottom cellar.

5-2-51

RECEIVED
STATE CORPORATION COMMISSION

MAY 2 - 1951

CONSERVATION DIVISION
Wichita, Kansas

Edmund Seal
District Conservation Agent

Date 4-30-51