

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 7 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Louis M. Mai
Complete Address Box 33, Russell, Kansas 67665
Lease Name Crawford Well No. # 10
Location NE NW SW Sec. 2 Twp. 14 Rge. 15 (E) (W) W
County Russell Total Depth 3308
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Southwest Casing Pulling Company
Address Box 364, Great Bend, Kansas License No. # 399
Operation Completed: Hour 10:30 A. Day May 67530
Month 8 9 Year 1971

The above well was plugged as follows:

12 1/2" csg. 905'. 7" csg. 3303'. Perf. 3072'.
Sanded hole back to 3000' & dumped 6 sax cement with dump bailer. Pulled pipe to
880', circulated hole with 5 sax hulls, 30 sax mud, plug, 2 sax hulls, & displaced
75 sax cement thru 7" csg. Pulled remaining pipe, set 20' rock bridge @ 320' &
displaced 75 sax cement. Mud to 60', set 10' rock bridge, & displaced 50 sax cement
with Halliburton Cementing Company's pump truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don L. Luman
Well Plugging Supervisor

DATE 9-8-71INV. NO. 4290-W