

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION Nw-Sw-NESEC. 2 TWP. 14 RGE. 15WDry Hole _____ Abandoned Oil Well ☒ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 9 Lease Johnson "A"Operator Cities Serv Oil Co. Address Box 751
Great Bend KansField _____ County RussellTotal Depth 2607 Feet.Plugging Contractor C.E. ShullPlugging Contractor's License No. 8Address Great Bend Kans

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 $\frac{1}{2}$ " @ 242' C.W.C. Oil string 4 $\frac{1}{2}$ " @
2606' w/150 sx Cem. Plugged back to 2478' and
top Perf. 2461' Sanded hole to 2450' and
dumped 3 sx Cem. Ripped off and pulled
4 $\frac{1}{2}$ " Casing mudded hole to 240' set r. bridge
and run 20 sx Cem. mud to 35' r. bridge
and 10 sx Cem to base of cellar

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 - 1954

CONSERVATION DIVISION
Wichita, Kansas

7-6-54

Warren H. Harner
District Conservation Agent

Date July 3, 1954