

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 132-33

LOCATION NE SW SW

SEC. 2 TWP. 14 RGE. 15

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 7 Lease Crawford

Operator Cities Service Co Address Russell, Kans

Field Gorham County Russell

Total Depth 3293 Feet.

(Describe briefly the manner in which the well was plugged)

12" at 910' - 7" at 3289'

6 sax cement run in bottom with dump bailer - pulled 2800'

7", mudded hole to 900' - pulled 250' of 12", mudded hole to

214', set wood plug, rock and 25 sax cement - mudded hole to

20', set rock bridge and 15 sax cement.

John [Signature] 1-18-50  
RECEIVED  
District Conservation Agent

Date 1-13-50 JAN 19 1950

**PLUGGING**  
FILE SEC 2 T 14 R 15  
BOOK PAGE 32 LINE 33