

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217RECEIVED
STATE CORPORATION COMMISSION
FEB 8 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Richard L. Mai

Complete Address Box 606, Russell, Kansas 67665

Lease Name Rouback Well No. # 12

Location SW SW NW Sec. 2 Twp. 14 Rge. 15 (E) W (W) W

County Russell Total Depth 3284

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas - License No. 462

Operation Completed: Hour 3:30 P.M. Day 5 Month 2 Year 1974

The above well was plugged as follows:

8 5/8" 914' Cwc. Set in Anhy.Sanded hole back to 2900' & dumped 5 sax cement with dump bailer. Pulled pipe.Mud to 375', set 25' rock bridge, & displaced 5 yds. Ready-mix Cement, cementing
from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 2/8/74
INV. NO. 8540-WSigned: David L. Linn
Well Plugging Supervisor

WELL LOG

COMPANY Sidey Oil Company

SEC. 2 T. 14S R. 15W
LOC. SW SW NW

FARM ROEBUCK

NO. 12

RIG. NO. 11

TOTAL DEPTH 3284'


COMM. 5-15-67

COMP. 5-24-67

SHOT OR TREATED

CONTRACTOR Murfin Drilling Company

ISSUED

COUNTRY Russell - Kansas
KANSAS

CASING

20	10
15	8 5/8" @914' w/450 sacks
12	6
13	5 1/2" @3284' w/200 sacks

ELEVATION

PRODUCTION Oil

FIGURES INDICATE BOTTOM OF FORMATIONS

150	Clay & Shale
360	Sand & Shale
505	Shale
775	Sand - Shale & Red Bed
904	Red Bed
949	Anhydrite
1090	Shale & Shells
1270	Shale - Shells
1550	Salt-Shale
1875	Shale & Lime
1945	Lime & Shale
2015	Shale & Lime
2205	Shale - Lime
2525	Shale & Lime
2540	Shale - Lime
2740	Shale & Lime
2800	Lime - Shale
2819	Lime & Shale
3284	Lime

RECEIVED
STATE CORPORATION COMMISSION
AUG 21 1973
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS

County of SEDGWICK

ss:

I, W. R. Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Roebuck #12 well.

Subscribed and sworn to before me this 1st day of

W. R. Murfin
June 19 67

My Commission Expires: ADELA MIZENER, Notary Public

My commission expires November 5, 1970

NOTARY PUBLIC