

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed November 9, 1967

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1967

11-27-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Lee Phillips Oil Company

Complete Address: 1532 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name Mease Well No. # 1

Location C SW NE Sec. 31 Twp. 30 Rge. 10 (E) (W) W

County Kingman Total Depth 4790'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sweetman Drilling Company

Address: Box 645, Great Bend, Kansas 67530 License No.

Operation Completed: Hour 6:30PM Day 21st Month November Year 1967

The Above well was plugged as follows:

247' of 8 5/8" surface pipe, cement circulated with 250 sacks. Hole was
filled with drilling mud to 235', 1st cementing plug, bridged with 2
sacks of dry cement and 1/2 sack of hulls on fluid at 235', and cemented with 23
sacks, with cement from 225' to 150'. Hole was filled with drilling mud to
40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack of hulls
on fluid at 40', and cemented with 9 sacks, with cement from 30' to the base
of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 11-28-67

INV. NO. 6764-W