

1 080455

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22, ³⁹⁴ 324 - 0000

SW NW NW, SEC. 5, T 22 S, R 11 (W) X

4950 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5210

Lease Name Sleeper Well # Q-1

Operator: Lebsack Oil Production, Inc.

County Stafford 116.48

Name & Address P. O. Box 489

Well Total Depth 3584 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:15 am Day: 26 Month: November Year: 19 85

Plugging proposal received from Norman Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 3578' Open Hole

1st plug sand back to 3520' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:30 am Day: 26 Month: November Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3520' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sack hulls, and 100 sx cement.

Maximum pressure 400 psi and shut in 100 psi

Remarks: Recovered 2571' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-6-85

INV. NO. 11295

12-5-85 DEC 5 1985