

9-26

1 040167

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,544-0000

S/2 SW NW, SEC. 5, T 22 S, R 11 W/E

2970 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5107

Lease Name Sleeper Well # 1A-5

Operator: H-30, Inc.

County Stafford

Name & Address 251 North Water, Suite 107

Well Total Depth 3660 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 268

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling, Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 8:30 p.m. Day: 25 Month: 9 Year: 19 88

Plugging proposal received from Dick Davis

(company name) H-30 Drilling, Inc. (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1755' GL
Anhydrite 560-80'

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1:15 a.m. Day: 26 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 3560' with 50 sx cement,

2nd plug at 580' with 40 sx cement,

3rd plug at 290' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

~~(XXX)~~ / did not observe this plugging.

DATE 10-6-88

Signed Stephen J. Pfeiffer
(TECHNICIAN)

REV. NO. 22523

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... September 10, 1988

API Number 15-185-22, 544-0000

OPERATOR: License # 5107
Name H-30, Inc.
Address 251 N. Water, Suite 10
City/State/Zip Wichita, KS 67202
Contact Person Jeffrey Burk
Phone (316) 263-2043

S/2 SW NW Sec. 5 Twp. 22 S. Rg. 11
2970 Ft. from South Line of Section
4620 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 660 feet
County Stafford

CONTRACTOR: License # 5107
Name H-30 Drilling, Inc.
City/State Wichita, Kansas

Lease Name Sleeper Well # 1A-5
Ground surface elevation 1755 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

Depth to bottom of fresh water 100'
Depth to bottom of usable water 225'
Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 250' +-
Conductor pipe required N/A
Projected Total Depth 3650' feet
Formation Arbuckle

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq, plus eventually plugging hole to KCC specifications.
Date 8/29/88 Signature of Operator or Agent Title Exploration Manager

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 250' feet per Alt. 1 X
This Authorization Expires 2-30-89 Approved By LKM 8-30-88

EFFECTIVE DATE 9-4-88

Move in 9-17-89 set 8 5/8" 2257

Sec. 5 Twp. 22 S. Rg. 11 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep... Top of Arbuckle or formation with 40 SX feet of 60/40 pozmix 6% gel
2nd plug @ ft. deep... 700' or formation with 50 SX feet of 60/40 pozmix 6% gel
3rd plug @ ft. deep... 280' or formation with 40 SX feet of 60/40 pozmix 6% gel
4th plug @ ft. deep... 40' or formation with 10 SX feet of 60/40 pozmix 6% gel
5th plug @ ft. deep... or formation with feet of

(2) Rathole to surface minus 5 feet 15 SX in rathole (b) Mousehole to surface minus 5 feet

NOTE: Agreement between

PUSHER Dick Davis
TD 3660 FORMATION Arb.
SURFACE PIPE 8 5/8" @ 268'
ANHYDRITE 500' ELEVATION 17556.4
STARTING TIME & DATE 8:50 P.M. 9-25-88
COMPLETION TIME & DATE 1:15 A.M. 9-26-88
1st PLUG @ 3560' FT. W/ 50 SX
2nd PLUG @ 580' FT. W/ 40 SX
3rd PLUG @ 290' FT. W/ 50 SX
4th PLUG @ 40' FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ 00 W.W. SX
CEMENT COMPANY Allied
TECHNICIAN

RECEIVED
STATE CORPORATE COMMISSION
SEP 27 1988
CONSERVATION DIVISION
Wichita, Kansas
60/40 poz 6% gel