

1052311
TO: STATE CORPORATION COMMISSION

4-19

API NUMBER 15-185-22,783-0000
N/2 NW SW SEC. 5, T 22 S, R 11 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4620 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SLEEPER WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 116.22

OPERATOR LICENSE # 4656

WELL TOTAL DEPTH 3576 FEET

OPERATOR: DAVIS PETROLEUM, INC PRODUCTION CSG: SIZE 4 1/2" @ 3575' WITH 150 SX

NAME AND RT 1, BOX 183 B SURFACE CASING: SIZE 8 5/8" @ 302' WITH 180 SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DS&W WELL SERVICING LICENSE NUMBER 6901

ADDRESS PO BOX 231 CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 19 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM KENT STRUBE

(COMPANY NAME) DS&W (PHONE) 316-587-3361

WERE: PERFS AT 3493-3501

1ST PLUG SANDED BOTTOM TO 3440' AND 4 SX CEMENT WITH A DUMP BAILER.

PUMPED PLUGS THROUGH THE CASING. 2ND PLUG AT 600' WITH 10 SX GEL - 40 SX CEMENT.

3RD PLUG AT 330' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 20 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:30 PM DAY: 19 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SANDED BOTTOM TO 3440' AND 4 SX CEMENT WITH A DUMP BAILER.

PUMPED PLUGS THROUGH THE CASING.

2ND PLUG AT 600' WITH 10 SX GEL - 40 SX CEMENT.

3RD PLUG AT 330' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 20 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1425' OF 4 1/2" CASING
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (D.D.) DESERVE THIS PLUGGING.

STATE CORPORATION COMMISSION

INVOICED

SIGNED Richard W. Lacy
APR 26 1999 (TECHNICIAN)

FORM CP-2/3 

DATE APR 29 1999

CONSERVATION DIVISION
Wichita, Kansas

4-26-99

INV. NO. 60894