

To: 1 120768
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-21
API NUMBER 15- 185-01,047-00-00
SW SW NE, SEC. 5, T. 22 S, R. 11 W
3025 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6030

Lease Name Sleeper D Well # 1

Operator: Ainsworth Operating Co.

County Stafford

Name & Address P.O. Box 1269

Well Total Depth 3566 115.89 feet

Colorado Springs, CO 80901

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 229

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Klima Well Service, Inc. License Number 7023

Address P.O. Box 386, Claflin, KS 67525-0386

Company to plug at: Hour: 8:30 a.m. Day: 21 Month: 1 Year: 19 93

Plugging proposal received from Bud Ainsworth

(company name) Ainsworth Operating Co. (phone) 316-262-5300

Work: 4 1/2" at 3562' w/160 sx cement, Perfs at 3478-3500', CIBP at 3475'

1st plug shoot casing and lay down 1 or 2 joints until casing frees up and spot 40 sx cement,
2nd plug pull all casing and pump through 8 5/8" surface casing with 500 lbs. hulls, 10 sx gel,
and 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 21 Month: 1 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug shot 4 1/2" casing at 1680' and laid down two joints and spotted 40 sx cement at 1600',

2nd plug laid down all 4 1/2" casing and pumped through 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 200 lbs. hulls and 150 sx cement.

Pumping pressure 0-400 psi and shut in 200 psi.

4 1/2" casing was collapsed at 2595'. Shot 4 1/2" casing 5 times from 2550-1680'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1680' of 4 1/2" casing.

INVOICED (If additional description is necessary, use BACK of this form.)

I (did ~~XXXXXX~~) observe this plugging.

DATE 2-4-93

Signed Duane Rankin (TECHNICIAN)

INV. NO. 37306

Rec'd 1-26-93