

To: 1 120467
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-16
API NUMBER 15-185-22,702-0000
App. 100' E
of NW NW SW SEC. 7, T 22 S, R 11 W
2310 feet from S section line
4850 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5107
Operator: H-30 Drilling, Inc.
Name & Address: 251 N. Water, Suite 10
Wichita, KS 67202

Lease Name Hammeke Well # 4-7
County Stafford 117.16
Well Total Depth 3605 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling, Inc. License Number 5107
Address 251 N. Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 12:15 a.m. Day: 16 Month: 9 Year: 19 90

Plugging proposal received from Jim Johnson
(company name) H-30 Drilling, Inc. (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 538'
1st plug at 600' with 50 sx cement, 2nd plug at 300' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 a.m. Day: 16 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement,
2nd plug at 300' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (with XXXXX) observe this plugging.

DATE 9-25-90

INV. NO. 29420

Signed Duane Rankin
(TECHNICIAN)

EFFECTIVE DATE: 8-15-90

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas 15-185-22,702-0000

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date August 21, 1990
month day year

100' East of
NW NW SW Sec 7 Twp 22 S, Rg 11 West

2310 feet from South line of Section
4850 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

OPERATOR: License # 5107
Name: H-30 Drilling, Inc.
Address: 251 N. Water, Suite 10
City/State/Zip: Wichita, KS 67202
Contact Person: Jeffrey A. Burk
Phone: 316-263-2043

County: Stafford
Lease Name: Hammeke Well #: 4-7
Field Name: Max. (Infield Disc.)

CONTRACTOR: License #: 5107
Name: H-30 Drilling, Inc.

Is this a Prorated Field? yes X no
Target Formation(s): Arbuckle
Nearest lease or unit boundary: 430'
Ground Surface Elevation: 1779 feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil Inj X Infield X Mud Rotary
Gas Storage Pool Ext Air Rotary
OWWO Disposal Wildcat Cable
Seismic: # of Holes

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 90'
Depth to bottom of usable water: 225'
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 250'
Length of Conductor pipe required: N/A

If OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth:

Projected Total Depth: 3650'
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
X well farm pond other

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

DWR Permit #: T89-156
Will Cores Be Taken?: yes X no
If yes, proposed zone: N/A

250' Alt. I Req.

Exp. 2/10/91

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101,

Pusher Jim Johnson
SPUD DATE 9-10-90 INIT. C.A.
LENGTH SURFACE PLANNED 250'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 3/8 @ 257 CONDUCTOR
ANHYDRITE T- 338 B- ELEVATION
TD 3605 FORMATION arb. log 3580
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 600 Ft. W/ SW SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ SW Ft. W/ SW SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN DR DATE 9-15-90
TYPE OF CEMENT 60-40-670
STARTING TIME 12:15 (AM/PM) DATE 9-18-1990
COMPLETION TIME 1:15 (AM/PM) DATE 9-18-1990
CEMENT COMPANY Allis
OR Undersigned

RECEIVED
SEP 18 1990
WICHITA