

12-6-96

2-010123

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-079-20,125-0000

SW NW NW, SECTION 24 TOWNSHIP 22 RANGE 2W

OPERATOR LICENSE # 5172 4290 FEET FROM S SECTION LINE
OPERATOR SCHULZ OIL & GAS INC 4950 FEET FROM E SECTION LINE
NAME & P.O. BOX 273
ADDRESS CANTON, KS 67428

LEASE NAME: BOESE #1
COUNTY: HARVEY
WELL TOTAL DEPTH: 3446' 112.00
PIPE:
SURFACE CASING: 8 5/8" @ 267'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: QUALITY WELL SERVICE INC

ADDRESS: 249 EAST BETH DRIVE, STERLING, KS 67579 LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 6 MONTH: 12 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: MITCH SCHULZ

COMPANY NAME: SCHULZ OIL & GAS INC PHONE: (316) 628-4431

WERE: SAND TO 3245' AND TOP WITH 5 SACKS OF CEMENT. SHOOT PIPE OFF AND PULL SAME. RUN TUBING TO 375' AND CIRCULATE CEMENT TO SURFACE.

PERFORATIONS AT 3294'- 3399'

5 1/2" CASING AT 3445'

PLUGGING PROPOSAL RECEIVED BY: JERRY CLARK

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { }

COMPLETED: HOUR: 12:30 DAY: 6 MONTH: 12 YEAR: 1996

ACTUAL PLUGGING REPORT: SANDED TO 3245' AND TOPPED WITH 5 SACKS OF CEMENT. SHOT PIPE OFF AT 2032' AND PULLED SAME. RAN 2 3/8" TUBING TO 372' AND CIRCULATED 240 SACKS OF CEMENT TO THE SURFACE; CEMENT FELL TO 155'. OPERATOR TOPPED WITH CEMENT.

RETRIEVED 2032' OF 5 1/2" CASING (62 JOINTS)

REMARKS: 60/40 POZ 2% GEL 2% CaCl₂ UNITED #3227

RECEIVED
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

INVOICED

MAY 21 1997

Michael R. Wilson
MICHAEL R. WILSON

DATE

5-21-97

CONSERVATION DIVISION
WICHITA, KS

FORM CP-2/3

INV. NO.

48155

REV. 3/90