

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-23239-00-01
Spot: N2SWSW Sec/Twnshp/Rge: 23-28S-4E
529 feet from S Section Line, 4629 feet from E Section Line
Lease Name: DAMETZ Well #: 3
County: BUTLER Total Vertical Depth: 2765 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2200		
PROD	5.5	2646		100 SX
PROD		2730		
SURF	8.625	229		120 SX

Well Type: SWD UIC Docket No: D27451.0 Date/Time to Plug: 11/28/2016 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: GEORGE RAYL Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/29/2016 12:50 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 1820'. DUMP BAILED 2 SXS CEMENT ON TOP. RIH ON WIRELINE, PERFORATED SQUEEZE @ 280'-281'. 4 SHOTS. RIH W/TBG @ 285', GRESSEL OILFIELD ESTABLISHED CIRCULATION, MIXED & PUMPED 120 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 12:50 AM, 11-29-2016. CEMENT TICKET #44852.

Perfs:

Top	Bot	Thru	Comments
2725	2880	CSG	

Remarks: D-27.451

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)