

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-20351-00-01  
Spot: NENWNW Sec/Twnshp/Rge: 26-28S-4E  
4950 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: GRAFF-DAMETZ Well #: 1  
County: BUTLER Total Vertical Depth: 2632 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2620		220 SX
SURF		200		
SURF	10.75	209		200 SX

Well Type: EOR UIC Docket No: E23888.1 Date/Time to Plug: 11/29/2016 8:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Revd. from: GEORGE RAYL Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE  
Date/Time Plugging Completed: 11/30/2016 4:15 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIN ON WIRELINE, SET CIBP @ 1690'. DUMP BAILED 4 SXS CEMENT ON TOP. RIH ON WIRELINE, PERFORATED SQUEEZE @ 260'-261'. 4 SHOTS. RIH W/TBG @ 265', GRESSEL OILFIELD ESTABLISHED CIRCULATION, MIXED & PUMPED 60 SXS 60/40 POZMIX 4% GEL. SDON. 11-30-2016, RIH W/TBG @ 265', GRESSEL OILFIELD ESTABLISHED CIRCULATION, MIXED & PUMPED 220 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 4:15 PM, 11-30-2016. CEMENT TICKET #44854.

Remarks:

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER  
(TECHNICIAN)

JAN 03 2017

Form CP-2/3

✓