

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-21723-00-01  
Spot: W2NWSWNE Sec/Twnshp/Rge: 36-10S-17W  
3580 feet from S Section Line, 2519 feet from E Section Line  
Lease Name: WHISMAN F Well #: 8  
County: ROOKS Total Vertical Depth: 3554 feet

Operator License No.: 5042  
Op Name: EDMISTON OIL COMPANY, INC.  
Address: 125 N MARKET STE 1420  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3536		250 SX
SURF	8.625	212		150 SX

Well Type: EOR UIC Docket No: E23922.2 Date/Time to Plug: 11/21/2016 8:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: SHANNON RAYBER Company: EDMISTON OIL COMPANY, INC. D Phone: (620) 793-2672

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
DV/Perforation: 2800' to surface.  
Perforations: 3354' - 3366', 3420' - 3440'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/21/2016 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3150' and pumped 150 sx cement w/400 # hulls. Pulled tubing to 1430' and pumped 120 sx cement w/100 # hulls to circulate cement to surface. Pulled all tubing and topped off 4 1/2" casing with 10 sx cement. Hooked to 8 5/8" x 4 1/2" annulus. Pressured to 300 psi immediately.

GPS: 39.14270 -099.16740

Perfs:

Top	Bot	Thru	Comments
3420	3440		
3354	3366		

Remarks: COPELAND ACID AND CEMENT TICKET # 44407

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

INVOICED

JAN 03 2017

Form CP-2/3

NOV 28 2016

KCC WICHITA  
DEC 19 2016  
RECEIVED

12-19-16