

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-001-02692-00-00  
Spot: SENWNWNW Sec/Twnshp/Rge: 11-24S-18E  
4700 feet from S Section Line, 4920 feet from E Section Line  
Lease Name: JAVAUX Well #: 2 C  
County: ALLEN Total Vertical Depth: 883 feet

Operator License No.: 32851  
Op Name: L & G PETROLEUM OPERATING, LLC  
Address: 1000 CAMINO DEL OESTE  
BAKERSFIELD, CA 93309

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.385	860		15 SX
SURF	8.25	34		0 SX

Well Type: EOR UIC Docket No: E09017.16 Date/Time to Plug: 11/04/2016 12:00 AM  
Plug Co. License No.: 33783 Plug Co. Name: MICHAEL DRILLING LLC  
Proposal Rcvd. from: RANDY STANLEY Company: Phone: (620) 365-9884

Proposed Plugging Method: get 1" beyond 500' and plug

Plugging Proposal Received By: WitnessType: NONE  
Date/Time Plugging Completed: 11/11/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2" casing to 550'. Hooked onto the 1" pipe and washed down to TD. Pumped and circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled the 1" pipe. Ran 1" pipe down the backside of the 2" casing to 250'. Pumped and circulated cement from 250' to surface on the backside of the 2" casing. Pulled the 1" pipe and topped the well off with cement. A total of 116 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED  
KCC DIST # 3  
DEC 19 2016  
CHANUTE, KS

RD

KCC WICHITA  
DEC 22 2016

RECEIVED

12-22-16

Remarks:

Plugged through: TBG

District: 03

Signed

  
E.C.R.S.  
(TECHNICIAN)

Form CP-2/3

INVOICED

JAN 03 2017