

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 8-37

LEASE NAME Johnson

WELL NUMBER 4

3630 Ft. from (S) Section Line

330 Ft. from (E) Section Line

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

SEC. 2 TWP. 14 RGE. 15 (E) of (W)

COUNTY Russell

LEASE OPERATOR Mai Oil Operations, Inc.

ADDRESS P.O. Box 33, Russell, Ks. 67665

PHONE# (913) 483-2169 OPERATORS LICENSE NO. 5259

Date Well Completed 8-37

Character of Well oil

Plugging Commenced 10-14-99

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-17-99

The plugging proposal was approved on 10-10-99 (date)

by Herb Deines, Dist. #4 (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Sent with Plugging Application

Producing Formation Topeka, Tarkio Depth to Top 2512 Bottom 2988 T.D. 2988

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		Surface	937	12 1/2"	not cmtd	
		Surface	3012	8 5/8"	not cmtd	
		Surface	3299	7"	cmtd, w/ 250 SKS	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Perforate 2 holes @ 1600' + 2 holes @ 940'. Hook up to 7" mix 75 SKS w/ 300# hulls 15 SKS gel + 200 SKS w/ 200# hulls. Displace to 950'. Perforate 2 holes @ 425'. Hook up to 7" mix 895 SKS cement, cement circ to surface between 7" + 8 5/8" + 8 5/8" + 12 1/2". All cement 60-90 Poz 10% gel. Cement fell down 170' mix 25 SKS Portland + Fillup.

Total 475 SKS cement + 15 SKS gel + 500# hulls Max PSI. 300#
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. N/A

Address Box 31, Russell, Ks 67665

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mai Oil Operations, Inc.

STATE OF Kansas COUNTY OF Russell, ss.

UCF-2 61994
10-26-94

Allen Bangert (Employee of Operator) of (Operator) above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Allen Bangert
(Address) P.O. Box 33, Russell, Ks. 67665

SUBSCRIBED AND SWORN TO before me this 24th day of October, 1994
Rita M. Clenney
Notary Public
My Commission Expires: December 17, 1995

