


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Russell County. Sec. 2 Twp. 14S Rge. 15 (W)
Location as "NE/CNW/SW" or footage from lines NE SW SE
Lease Owner. Murfin Drilling Company
Lease Name. Sullivan "B" Well No. 2
Office Address. 617 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed June 15 19 50
Application for plugging filed March 31 19 70
Application for plugging approved April 17 19 70
Plugging commenced April 21 19 70
Plugging completed April 21 19 70
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production January 19 68
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation Depth to top Bottom Total Depth of Well 3305' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom of hole was plugged off in 3-13-68 by Ace Pipe Pulling when they started to pull pipe. PB from 2957 to 2927' w/sand. Run tubing in hole to 2100' - Mixed and pumped 25 sacks Gel through tubing. Pulled tubing to 300', mixed and pumped 50 sacks of cement through tubing. Pulled tubing. Complete on 4-13-70 by orders of Don Truan, Russell, Kansas.

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Co., Russell, Kansas
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James R. Daniels (employee of owner) or (owner or operator) of the above-described

well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

James R. Daniels
617 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of April, 19 70

L. ANNE SWALWELL, Notary Public
My commission expires Sept. 23, 1972

L. Anne Swalwell
Notary Public.

DRILLING LOG

To: John Lindas Oil, Inc. et al
1316 Union National Bank Building
Wichita 2, Kansas

Lease: Sullivan #2

County: Russell, Kansas
Section: 2-14S-15W
Location: NE SW SE

Rotary Total Depth: 3305'

Commenced: 5-31-50 Completed: 6-15-50

Casing: 8-5/8" @ 154' W/100 sacks cement and 1 C.C.
5-1/2" @ 3303' W/100 sacks cement

Contractor: John Lindas Oil, Inc.
1316 Union National Bank Building
Wichita, Kansas

FIGURES INDICATE BOTTOM OF FORMATIONS

0	to	40	Surface Clay
40		60	Sand
60		157	Shale & Shells
157		360	Blue Shale
360		445	Sand
445		500	Iron & Sand
500		550	Sand
550		560	Shale
560		910	Red Bed & Shells
910		946	Anhydrite
946		1570	Shale & Shells
1570		1790	Broken Lime
1790		2115	Lime
2115		2185	Lime & Shale
2185		2440	Shale & Lime
2440		2575	Shale & Lime Shells
2575		2670	Lime & Shale
2670		2718	Shale
2718		2745	Lime & Shale
2745		2775	Shale
2775		3253	Lime
3253		3303	Lime & Shale
3303		3305	T.D. Arbuckle Dolomite

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1970
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above statement and log is true and correct record and log of the well drilled at the location above described.

JOHN LINDAS OIL, INC.

By Scott Shuckey

Subscribed and sworn to before me this 19th day of June, 1950.

Catherine Dancy

My commission expires March 25, 1952.