


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County, Sec. 35 Twp. 30 Rge. (E) 10 (W)  
Location as "NE/CNW/SW" or footage from lines \_\_\_\_\_  
Lease Owner Barbara Oil Company  
Lease Name Morisse Well No. 1  
Office Address 509 Union Center Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 18, 19 68  
Application for plugging filed June 18 (Telephone) 19 68  
Application for plugging approved June 18 19 68  
Plugging commenced June 19 19 68  
Plugging completed June 19 19 68  
Reason for abandonment of well or producing formation Hole dry



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production - 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ralph Warren  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4470 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand		0	150	8 5/8"	150'	None
Shale		150	256	8 5/8	256	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud & 1/2 sack hulls. Set plug & put in 25 sacks of cement. Filled hole with mud and 1/4 sack hulls to 40 feet. Set plug & 10 sacks of cement to bottom of cellar. Put 2 sacks of cement in rathole. Job completed at 3:15 A.M. June 19, 1968 by Mr. Ralph Warren, State pluggger of Pratt, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 28 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.  
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
R. Douglas Myers (employee of owner) or (owner or operator) of the above described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Douglas Myers  
509 Union Center Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of June, 1968

Doris Oglesbee  
Doris Oglesbee  
Notary Public

My commission expires August 12, 1971



**GABBERT-JONES, INC.**  
**WICHITA, KANSAS**  
**DRILLERS' WELL LOG**

MORISSE #1  
 C NE NE SECTION 35-30S-10W  
 KINGMAN COUNTY, KANSAS

COMMENCED: JUNE 8, 1968  
 COMPLETED: JUNE 19, 1968

OPERATOR - BARBARA OIL CO.

DEPTH	FORMATION	REMARKS
FROM	TO	
0	100	SAND
100	256	RED BED RAN 7 JOINTS 8-5/8" CASING, SET @ 256' #1/200 BAGS CEMENT.
256	600	RED BED
600	1308	RED BED AND SHALE
1308	1316	ANHYDRITE
1316	1555	SHALE, SHELLS AND LIME
1555	2615	SHALE AND LIME
2615	2700	SANDY SHALE AND LIME
2700	2760	SHALE AND LIME
2760	2960	LIME
2960	3815	LIME AND SHALE
3815	4220	LIME
4220	4335	LIME AND SHALE
4335	4382	LIME
4382	4400	CHAT
4400	4437	CHERTY LIME
4437	4470	LIME
4470	TD	DRY AND ABANDONED.

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 28 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C NE NE SECTION 35-30S-10W, KINGMAN COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

*E. E. Hall*  
 E. E. HALL

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 21ST DAY OF JUNE, 1968, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

*Barbara J. Layton*  
 BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1972.

