

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-24,406

LEASE NAME ROUS

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3630' Ft. from S Section Line

2970' Ft. from E Section Line

SEC. 28 TWP. 16SRGE.11 (X) or (W)

COUNTY BARTON

Date Well Completed 2-10-90

Plugging Commenced 7-25-90

Plugging Completed 7-25-90

LEASE OPERATOR HAR-KEN AGENT OK

ADDRESS 2932 NW 122nd Bradley Square No. 16
Oklahoma City, OK 73120

PHONE# (405) 752-0318 OPERATORS LICENSE NO. 9911

Character of Well XX

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 25, 1990 (date)

by Herb Deines District 4 (KCC District Agent's Name).

Is ACO-1 filed? by operator If not, is well log attached? _____

Producing Formation never produced Depth to Top _____ Bottom T.D. 3455'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

STATE CORPORATION COMMISSION
RECEIVED
JUL 30 1990

Formation	Content	From	To	Size	Put in	Pulled out
surface		0	401	8 5/8"	401'	none
production		0	3455'	5 1/2"	3455'	2540'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

In accordance with plugging orders from District 4 we sanded to 3300' with 18 sx. of frac sand and dumped 5 sx. cement on top. Shot pipe @ 2540' and pulled out. Pumped 250 sacks of 65/35 Pozmix, 8% Gel, 1/4# flo seal per sack With 500# hulls.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Cementing Company License No. _____

Address Great Bend, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Har-Ken Agent OK

STATE OF KANSAS COUNTY OF BARTON, ss.


L. D. Davis (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. D. Davis
L. D. Davis

(Address) Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 26th day of July, 1990



Notary Public
Bessie M. DeWerff

My Commission Expires: 5-20-93