


Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Barton County, Sec. 28 Twp. 16 Rge. 11 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner West Supply Co., Inc.
Lease Name Community Selma Seyfert "C" Well No. 3
Office Address Chase, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 6-24-63 19____
Plugging completed 6-27-63 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3364 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	120'	None
				7"	3348'	2492'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3364', sanded to 3340' and dumped 5 sacks of cement @ 3340' with dump bailer. Pulled 7" casing to 350' and pumped 10 sacks of gel mud. Pulled 7" casing to 300' and pumped in 20 sacks of cement. Pulled 7" casing to 130' and pumped in 20 sacks of cement. Pulled balance of 7" casing, bailed hole to 20' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

JUL 1 1963

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas

SUBSCRIBED AND SWORN TO before me this 28th day of June, 1963

My commission expires May 20, 1964 Milton J. Volin Notary Public.

INVOICED
DATE 7/1/63
INV. NO. 7332-W