

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-009-03102-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Barton SEC. 28 TWP. 16s RGE. 11w E/W
 Location as in quarters or footage from lines:
W/2 NE SW NW WASENW AUB KCC

Locate Well
 correctly on above
 Section Platt.

Lease Owner Kaiser-Francis Oil Company
 Lease Name Seyfert #1 Well No. _____
 Office Address P.O. Box 35528, Tulsa, Okla, 74135
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 1/15/83
 Plugging completed 1/28/83
 Reason for abandonment of well or producing formation _____

_____ Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3361'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	251'	none
				5 1/2"	3357 1/2'	2353'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged bottom with 5 sacks cement, sand to 3300' & ran 5 sacks cement.
Shot pipe at 2710', 2610', 2510', & 2407'. Pulled total of 72 joints.
Plugged well with 4 sacks hulls, 12 gel, 65 cement, 3 gel, 1 hull, plug,
and 100 cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
 Box 347, Chase, Ks, 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of February, 1983

My Commission expires:



RECEIVED
 Notary Public

FEB 14 1983
 02.14.83

Wichita, Kansas

See other side for
distribution

DRILLER'S LOG

COMPANY: Herman George Kaiser, Oil Producer
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: SEYFERT #1
 LOCATION: W/2 SE NW Sec. 28-16S-11W
 BARTON COUNTY, KANSAS
 COMMENCED: 1-21-64
 COMPLETED: 1-27-64

0	150	Shale
150	1545	Shale & Shells
1545	2500	Lime & Shale
2500	2705	Shale & Lime
2705	3000	Lime & Shale
3000	3361	Lime
	<u>3361</u>	<u>Rotary Total Depth - Set 5 1/2" Casing</u>

Set 8 5/8" used surface casing @ 251' with landing joint cemented with 175 sacks Sunset.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Seyfert #1 well, located in the West half of SE NW of Section 28, Township 16 South, Range 11 West, in Barton County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 29th day of January, 1964.

HELLA F. BELL
Ulanda Nichols
 Ulanda Nichols, Notary Public

My Commission Expires: April 1, 1967

Distribution:

FILE COPY

RECEIVED
STATE CONSERVATION COMMISSION

OCT 12 1982

CONSERVATION DIVISION
Wichita, Kansas