

15-185-01011-0000

Information Completely
Furnished Affidavit
Cover Report to:
Conservation Division
State Corporation Commission
10th Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 4 Twp. 25 Rge. 14 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW SW SE
Lease Owner Aylward Drilling Co.
Lease Name Spencer Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2-18-61 _____ 19____
Plugging completed 2-28-61 _____ 19____
Reason for abandonment of well or producing formation Depleted.

NORTH

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

State well correctly on above
Section Plat

Conservation Agent who supervised plugging of this well Frank Broadfoot.
Formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4179 Feet
and thickness of all water, oil and gas formations.

ROCK OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	270'	None
				4-1/2"	4186'	3637'

Describe in detail the manner in which the well was plugged, indicating where cement or other plugs were used, and state the character of each plug set.

Feet to

Checked hole to 4179', from 4179' to 4100' and dumped 4 sacks cement @ 4100' with dump bailer. Pulled 4 1/2" casing. Bailed 8-5/8" casing from surface to 200', set 10' rock bridge 190' and ran 20 sacks of cement. Mudded to 40', set 10' rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

APR 21 1961

4-21-61

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of February, 1961

Milton J. Volin
Notary Public

My commission expires May 20, 1964

SPENCER #1

Casing Record:

Company: Aylward Drilling Company
Contractor: Aylward Drilling Company

Location: NW SW SE 4-25-145
Stafford County,
Kansas

8 5/8" - 273'
4 1/2" - 4186'

Commenced: December 15, 1960
Completed: December 27, 1960

Elevation: 1986 K.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	0	15	Set 8 5/8" @ 273' w/225 sacks cement
Sand	15	110	
Shale	110	273	Geological Tops: (Log)
Red Bed	273	560	
Red Bed & Sand	560	580	Heebner 3557
Red Bed & Shale	580	810	Toronto 3581
Anhydrite Stringers	810	930	Douglas 3599
Shale & Shells	930	1650	Brown Lime 3701
Shale & Lime	1650	1805	Lansing 3727
Lime	1805	1888	Base Kansas City 3995
Lime & Shale & Shells	1888	1949	Mississippian 4112
Lime w/Shale & Clay	1949	1980	Kinderhook 4173
Shale & Lime	1980	2175	R.T.D. 4187
Lime	2175	2210	
Shale & Lime	2210	2260	DST 3860-3933 Open 1 hr.
Lime	2260	2355	Rec. 1200' SW
Lime & Shale	2355	2395	IBHP 1120#/20" - FBHP 1115#/30"
Shale & Lime	2395	2550	FP 110#-480#
Shale w/Lime	2550	2730	
Shale & Lime	2730	2895	DST 4113-31 Open 1 hr.
Lime & Shale	2895	3290	Rec. 50' 51GM w/few specks oil
Shale & Lime	3290	3400	420' gas 12 pipe
Lime & Shale	3400	3424	IBHP 180#/20" - FBHP 95#/30"
Shale & Sand	3424	3465	FP 0#-0#
Lime & Shale	3465	3620	
Lime	3620	4160	Set 4 1/2" casing @ 4186 w/700 gal
Lime w/shale & Chert	4160	4201	T.D.

Perf. from 4113 to 4140, 3 shot per ft.
Acidized: 1000 mud acid.
Frac. w/10,000 oil & 10,000# sand
Hole full water w/scum oil (lack 75-100 bbl of load oil)

D & A

RECEIVED
STATE CORPORATION COMMISSION

APR 21 1961

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of knowledge.

Charles D. Williams

Subscribed and sworn to before me this 18th day of January, 1961

Duane Jessup
DUANE JESSUP Notary Public

My commission expires December 11, 1961