


STATE OF KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 P. O. BOX 17027
 WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Harvey County. Sec. 24 Twp. 22 Rge. 2 W (E) (W)
 Location as "NE/CNW&SW" or footage from lines. N/2 NW NW
 Lease Owner: Tomlinson Oil Co. Inc.
 Lease Name: Boese Well No. 2
 Office Address: 200 W. Douglas Suite 1030 Wichita, Ks 67202
 Character of Well (completed as Oil, Gas or Dry Hole) oil
 Date well completed 5-19-1970
 Application for plugging filed 10-16-1975
 Application for plugging approved 10-17-1975
 Plugging commenced 10-24-1975
 Plugging completed 10-28-1975
 Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes- Hugh Scott

Name of Conservation Agent who supervised plugging of this well Hugh Scott
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3481' Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,626'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Used Allied Cementing Co. Pumped:

3 sx of hulls

15 sx of Gel

75 sx of cement w 2% Gel

Pump pressure 500 lbs.

Close-in pressure 250 lbs.

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Art Lamb Casing Pulling Inc.
 Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas COUNTY OF Reno, ss.
 Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
 2809 King St. Hutchinson, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October, 1975

My commission expires December 31, 1977

Judy Lamb
 Notary Public.

RECEIVED
 STATE CORPORATION COMMISSION

NOV 3 1975

11-3-75

CONSERVATION DIVISION
 Wichita, Kansas

DRILLERS LOG

COMPANY: Tomlinson Oil Co., Inc.
 CONTRACTOR: Aspen Drilling Co.
 LEASE NAME: Boese #2
 LOCATION: N/2 NW NW Sec. 24-22S-2W
 Harvey County, Kansas
 ELEVATION: 1470' K.B.
 SURFACE CASING: 13 jts. (269') 8 5/8"
 OIL STRING: 107 jts. (3493') 5 1/2"
 COMMENCED: May 10, 1970
 COMPLETED: May 19, 1970
 ROTARY TOTAL DEPTH: 3481'

<u>FORMATION</u>	<u>DEPTH</u>
Clay	20
Sand	115
Shale	277
Lime	430
Lime & Shale	2465
Lime	2745
Lime & Shale	3155
Lime	3238
Lime & Chert	3305
Lime	3320
Lime & Shale	3403
Lime	3466
Simpson	3481

Ran 13 jts. (269') 8 5/8" casing set at 276' with 200 sacks cement. Cement circulated.

DST #1 3282-3305
 Cored 3431-3481
 Ran electric log.

Ran 107 jts. (3493') 5 1/2" casing set at 3480' with 100 sacks cement.

RECEIVED
 STATE CORPORATION COMMISSION

AFFIDAVIT

OCT 17 1975

State of Kansas)
) ss:
 County of Barton)

CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle
 William S. Schachle, AFFIANT

Subscribed and sworn to before me this 20th day of May, 1970.

Theora Holleman
 Theora Holleman, Notary Public

My commission expires: April 18, 1972.