

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Reno County, Sec. 9 Twp. 22 Rge. 8 (E) W (W)

Location as "NE/CNW/SW" or footage from lines E/2 NE SW

Lease Owner Thomas H. Allan

Lease Name McKee (Salt Water In Section Well) Well No. 1

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 1-9-63 19

Plugging completed 1-15-63 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Herman Justus

Producing formation Depth to top Bottom Total Depth of Well 3475 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	195'	None
				5-1/2"	3466'	2815'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded hole to 3450' and dumped 5 sacks of cement @ 3450' with dumpbailer. Pulled 5 1/2" casing, set rock bridge @ 190' and dumped 20 sacks of cement with dump bailer. Set rock bridge @ 40' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1963

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or (owner or operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of January, 1963

Milton J. Volin Notary Public.

My commission expires May 20, 1964



Original

8 5/8" @ 195' - 130 Sx
5 1/2" @ 3466' - 75 Sx

ALLAN ET AL #1 McKEE
E 1/2 NE SW 9-22-8W
Sterling Pool, Reno Co., Kansas
COMM: 8/4/54. COMPL: 9/13/54
CONTRACTOR: Tom Allen
ELEVATION: 1681 RB

I.P. Swab 16 bbl. Oil and
40 bbl. Water/day

All Depths from Rotary Bushings

0 - 45 Soil
120 Sand
160 Yellow Clay
195 Red Beds
600 Red Shale
800 Blue Shale
1100 Salt & Shale
1200 Shale
1300 Anhydrite
2600 Shale & Shells
2900 Lime & Shale Breaks
3028 Shale
3035 Brown Lime
3054 Shale
3095 White Lime
3097 Oolitic Lime
3165 Lime
3171 Oolitic Lime
3205 Lime & Shale Breaks
3230 Lime
3233 Oolitic Lime
3250 Lime
3260 Shale
3300 Lime
3302 Oolitic Lime
3325 Lime
3335 Shale
3345 Cherty Lime
3365 Lime & Shale
3402 Lime
3456 Shale & Lime Shells
3460 Red Mud
3463 Red Cherty Conglomerate
3466 White & Orange Weathered Chert
CHANGED TO CABLE TOOLS
3484 Same partly saturated with show
free oil
3487 (T.D.) White Vitreous Chert
Water 1 bbl./hr.
Plug back to 3475

FORMATION TOPS:

3028 Brown Lime
3054 Lansing
3463 Mississippi

SAND OIL TREATED 3466-3475
Swab 16 bbl. Oil 40 bbl. Water
per day

RECEIVED
STATE CORPORATION COMMISSION

JAN 8 1963

CONSERVATION DIVISION
Wichita, Kansas