


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Kingman County. Sec. 25 Twp. 30 Rge. (E) 10 (W)

Location as "NE/CNW/SW" or footage from lines C SW SE
Lease Owner Barbara Oil Company
Lease Name Robinson Well No. 1
Office Address 509 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 8 1968
Application for plugging filed November 8 1968
Application for plugging approved November 8 1968
Plugging commenced November 8 1968
Plugging completed November 8 1968
Reason for abandonment of well or producing formation



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren
Producing formation Depth to top Bottom Total Depth of Well 4476 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	242'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 245'. Followed by wooden plug and 25 sacks cement. Mud to 40' and 1/2 sack of hulls and 10 sacks cement. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.


I, _____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Subscribed and sworn to before me this 13th day of November, 1968 (Address)

My commission expires August 12, 1971

[Signature]
Doris Oglesbee
Notary Public.



NOTARY PUBLICS' LOG

OPERATORS

Barbara Oil Company
500 Union Center Bldg.
Wichita, Kansas 67202

DRILLING COMMENCED: 11-1-68

CONTRACTORS

Graves Drilling Co., Inc.
505 Union Center Bldg.
Wichita, Kansas 67202

DRILLING COMPLETED: 11-3-68

CASINGS RECORDED: 7 jts., 2 1/2" - 8 1/2"
cemented with 200 sacks cement

LOCATION: Robinson #1
C 87 53, Sec. 29, 503, 100
Kingman County, Kansas

0	-	118	Sand and shale
118	-	245	Red bed
245	-	760	Shale
760	-	925	Shale and chert
925	-	1513	Shale
1513	-	1620	Lime
1620	-	1928	Shale and chert
1928	-	2428	Shale
2428	-	2568	Lime
2568	-	3121	Shale and chert
3121	-	3516	Lime
3516	-	3608	Shale
3608	-	3800	Sand
3800	-	4120	Lime
4120	-	4391	Shale
4391	-	4470	Lime and chert

RECEIVED
STATE CORPORATION COMMISSION
NOV 13 1968
CONSERVATION DIVISION
Wichita, Kansas

NOT AND ANSWERED

I hereby certify the foregoing statements to be true and correct, to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves
President

STATE OF KANSAS

WICHITA COUNTY

558

NOTARY PUBLIC
DORIS OGLESBEE
WICHITA, KANSAS

Presented and sworn to before me, a Notary Public, this 12th day of November, 1968

My Commission expires Aug. 12, 1971

Doris Oglesbee
Notary Public