


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH



Locate well correctly on above  
Section Plat

Kingman County, Sec. 26 Twp. 30 Rge. 10 (E) (W)X  
Location as "NE/CNW/SE" or footage from lines C/NW/SE  
Lease Owner Barbara Oil Company  
Lease Name Cox Well No. 1  
Office Address 509 Union Center Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced November 30, 1972  
Plugging completed December 7, 1972  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 4545 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	250	None
				5 1/2	3256	2159.00'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured T.D. at 2590 ft. Dumped sand to 2550 ft. and 5 sacks cement. Shot casing at 2400, 2300, 2200, 2100 and 2030 ft. Pulled 65 jts. of 5 1/2" casing. Built a rock bridge at 240 ft. and dumped 25 sacks cement. Mudded hole to 40', dumped a 10' rock bridge and capped well with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 12 1972

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.  
Address P. O. Box 698 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.

James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

James W. Rockhold

Box 698 Great Bend, Ks. 67530  
(Address)

James W. Rockhold

SUBSCRIBED AND SWORN TO before me this 11th day of December, 1972

Cathy Miller

Cathy Miller Notary Public.

My commission expires September 30, 1975

ROTARY DRILLERS' LOG

OPERATOR: Barbara Oil Company  
509 Union Center  
Wichita, Kansas

DRILLING COMMENCED: April 15, 1968

CONTRACTOR: Graves Drilling Co., Inc.  
505 Union Center  
Wichita, Kansas

DRILLING COMPLETED: April 25, 1968

CASING RECORD: 7 Jts. 250' 8-5/8"  
cemented with 200 sacks  
99 Jts. 3256' 5-1/2"  
cemented with 150 sacks

LOCATION: Cox No. 1  
C NW SE  
Section 26-30S-10W  
Kingman County, Kansas

0 - 120	Sand
120 - 250	Red bed
250 - 980	Red bed & shale
980 - 1509	Shale, lime & shells
1509 - 2590	Lime & shale
2590 - 2675	Sand & shale
2675 - 2780	Shale & sand
2780 - 3116	Lime & shale
3116 - 3252	Sand
3252 - 3494	Shale & lime
3494 - 3537	Lime & shale
3537 - 3608	Shale & lime
3608 - 3716	Shale & sand
3716 - 3736	Lime & shale
3736 - 4212	Lime
4212 - 4376	Lime & shale
4376 - 4465	Lime
4465 - 4545	Shale
4545	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 31 1972  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves  
President

STATE OF KANSAS )  
                  ) SS:  
SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public, this 29th of April, 1968.

Betty Brandt  
Betty Brandt Notary Public

My commission expires: May 9, 1971.