

WELL PLUGGING RECORD  
K.A.R.-82-3-117

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

TYPE OR PRINT  
NOTICE: Fill out Completely  
and return to coms. div.  
office within 30 days.

API NUMBER 15-095-21770-0000  
LEASE NAME Anthony A  
WELL NUMBER 1  
660 ft. from S Section Line  
~~XXXX~~ 4620 ft. from E Section Line  
SEC. 34 TWP. 30 RGE. 10 (E) or (W)  
COUNTY Kingman

LEASE OPERATOR R & B Oil & Gas, Inc.  
ADDRESS PO Box 195, Attica, KS 67009  
PHONE # (620) 254-7251 OPERATORS LICENSE NO. 31191

Character of well  Gas  
(Oil, Gas, D&A, SWD, input, Water Supply Well)

The plugging proposal was approved on 2/15/02  
by Doug Louis (XCC District Agent's Name)

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation Mississippi Depth to Top 4406 Bottom 4494 T.D. 4546  
Show depth and thickness of all water, oil and gas formations  
OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	Gas	4406	4418	8 5/8	255	none
				4 1/2	4538	2517

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set  
Sand at 4351, baled 4 sks cem. Shot pipe at 3817, 3641, 3221, 2700, 2517, work free. Pull pipe to 1600, pump 35 sacks cement. Pull to 1150, pump 35 sacks cement. Pull to 300 and circulate cement to surface with 150 sacks. Pull rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925  
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R & B Oil & Gas, Inc.  
STATE OF Kansas COUNTY OF Harper, ss.

Randy Newberry (Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filed that the same are true and correct, so help me God.


(Signature) Randy Newberry  
(Address) PO Box 195, Attica, KS 67009

SUBSCRIBED AND SWORN TO before me 5th day of April, 2002

Rebecca S. Newberry Notary Public

My commission Expires: 7-21-2005

Form CP-4  
Revised 05-88



OR