

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Reno County, Sec. 21 Twp. 22S Rge. 7W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW

Lease Owner The Texas Company

Lease Name T. H. McVay Well No. 1

Office Address 614 Bitting Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed October 28 19 53

Application for plugging filed October 28 19 53

Application for plugging approved October 28 19 53


Plugging commenced October 28 19 53

Plugging completed October 28 19 53

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3948' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	330'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGED AS FOLLOWS:

- 3948' to 185' - Heavy Mud
- 185' - Bridging Plug
- 185' to 145' - 25 Sacks Cement
- 145' to 10' - Heavy Mud
- 10' to Bottom of Cellar - 5 Sacks Cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Noble Drilling Company
Address Stanolind Building, Tulsa, Oklahoma

STATE OF Kansas COUNTY OF Sedgwick ss.
M. C. Harrell (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. C. Harrell
614 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of November 19 53

H. Howard Kistler Notary Public.

My commission expires September 20, 1956

24-7366-5 3-53-20M

PLUGGING

FILE SEC 21 T 22 R 7W

BOOK PAGE 139 LINE 10

RECEIVED

STATE CORPORATION COMMISSION

11-20-53

LOG OF WELL

T. H. McVAY NO. 1

SHEET 1

OWNER The Texas Company DIVISION Oklahoma DATE MADE November 19, 1953
 DISTRICT Kansas LEASE T. H. McVay WELL NO. 1
 STATE Kansas COUNTY OR PARISH Reno TWP. 22S RANGE 7W SEC. 21
 LOCATION OF WELL SW SW NW

COMMENCED RIGGING UP 10-14-53 COMMENCED DRILLING 10-15-53 COMPLETED DRILLING 10-28-53
 DAY DRILLER _____ NIGHT DRILLER _____ CONTRACTOR Noble Drilling Co.
 CABLE FROM _____ TO _____ ROTARY FROM 0' TO 3948' COMPANY RIG NO. _____
 TOTAL DEPTH 3948' MEASURED BY M. C. Harrell ELEVATION KB - 1597'
DR - 1597'

CASING RECORD

GL - 1592'

SIZE	WEIGHT	PUT IN WELL		PULLED OUT		LOST IN WELL		SHOES		PACKERS			
		FEET	INS.	FEET	INS.	FEET	INS.	LENGTH	MAKE	KIND	LENGTH	SET AT	
10-3/4"	32.75#	330'						(H-40, new casing)					FT.
													FT.
													FT.
													FT.
													FT.
													FT.
													FT.
10-3/4" casing set at 328' with 200 sacks cement and 2 sacks G.C. Cement													FT.

circulated.

WAS CASING CEMENTED? _____ IF SO, HOW MANY SACKS OF CEMENT USED? _____
 LINER: STATE SIZE AND WEIGHT _____ WHERE SET _____ FT. AND INS. BLANK _____ FT. AND INS. PERFORATED _____
 HOW PUT TOGETHER _____ COUPLING _____ FLUSH JOINT _____ INSERTED _____
 REMARKS: _____

EQUIPMENT RECORD

TUBING				SUCKER RODS			PUMPING OUTFIT
SIZE	WEIGHT	FEET	INS.	FEET	INS.	SIZE AND KIND	DESCRIPTION, KIND, SIZE, ETC.
Completed Plugging 10-29-53							

FLOWING, PUMPING, GASSEY OR DRY Dry PRODUCTION FIRST 24 HOURS _____ PRODUCTION SETTLED _____
 IF GAS WELL, OPEN FLOW CAPACITY _____ SHUT IN PRESSURE _____ ROCK PRESSURE _____
 KIND OF SHOT _____ SIZE OF SHOT, QUARTS _____
 NUMBER OF SHELLS _____ SIZE OF SHELLS _____ INCHES, DIAMETER _____
 LENGTH OF SHELLS _____ FEET _____ INCHES _____ TOP OF SHOT _____
 BOTTOM OF SHOT _____ ANCHOR _____ WELL BRIDGED TO _____
 TOTAL DEPTH OF WELL _____ NUMBER OF SHOT _____ PRODUCTION BEFORE SHOT _____ BBLs. PER DAY _____
 PRODUCTION AFTER SHOT _____ BBLs. PER DAY. SHOT FURNISHED BY _____
 NAME OF SHOOTER _____ SHOT INSPECTED _____ BY _____ (COMPANY EMPLOYEE)
 COMMENCED DRILLING DEEPER _____ COMPLETED _____ DRILLING DEEPER _____
 TOTAL DEPTH _____ PRODUCTION FIRST 24 HOURS _____ PRODUCTION SETTLED _____

REMARKS: T. H. McVay #1
Wildcat
TD 3948'
Completed Drilling 10-28-53
Completed Plugging 10-29-53

NOTE: IF WELL WAS DRY, STATE UNDER REMARKS, WHEN, HOW, AND BY WHOM PLUGGED.
 STATE UNDER REMARKS ANYTHING OF INTEREST NOT COVERED IN LOG.
 IF THE SPACE PROVIDED FOR REMARKS IS NOT SUFFICIENT WRITE ON BOTTOM OF LAST SHEET OF LOG.

LOG OF WELL

SHEET No. 2

District Oklahoma Owner The Texas Company Farm T. H. McVay Well No. 1

FORMATION	AMOUNT	COLOR	HARD OR SOFT	DEPTH CORES TAKEN	REMARKS
REMARKS:					
10-21-53					Ran DST #1 from 2892-2910', open 1 hour, had weak blow, recovered 70' salty mud. SBHP 1200# in 30 minutes.
10-24-53					Attempted to run DST #2 from 3460-70', open 1 hour, had weak blow for 14 minutes, misrun.
10-25-53					Ran DST #3 from 3465-80', open 1 hour, recovered 90', slightly gas cut mud. SBHP 200# in 30 minutes.
10-27-53					Ran DST #4 from 3793-3815', open 1-1/2 hours, recovered 430' salt water. SBHP 1395# in 30 minutes.
10-29-53					Drilled to 3948' in Arbuckle, no show. Well plugged and abandoned.
TOPS:					
					Topeka-----2430'
					Heebner-----2745'
					Douglas-----2771'
					Brown Lime-----2939'
					Lansing-----2957'
					Mississippi-----3458'
					Kinderhook-----3525'
					Maquoketa-----3724'
					Simpson-----3775'
					Arbuckle-----3874'

PLUGGING
 FILE SEC 21-T-22276
 BOOK PAGE 139 LINE 10