

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-4-68

RECEIVED
STATE CORPORATION COMMISSION

3-22-77

MAR 22 1977

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 145 - 20,445 - 0000 (of this well)

Operator's Full Name Abercrombie Drilling, Inc.

Complete Address 801 Union Center, Wichita, Kansas

Lease Name Wesley Well No. 1

Location NE NW SE Sec. 11 Twp. 22 Rge. (E) (W) 15

County Pawnee Total Depth 3970'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 5 P Day 16 Month 3 Year 1977

The above well was plugged as follows:

RTD 3970' 8 5/8 csg set 223' cwc 200 sx. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 420' thru drill pipe.

Heavy mud to 215' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 3-22-77

INV. NO. 4834-w