

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name F & M Oil Company

Complete Address 603 Union Center Wichita, Kansas 67202

Lease Name Branstetter Well No. 1

Location NE NW NW Sec. 11 Twp. 22 Rge. (E) (W) 15

County Pawnee Total Depth 3958'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor B - B Drlg.

Address Wichita, Kansas License No.     

Operation Completed: Hour 3:45 P Day 9 Month 4 Year 1971

The above well was plugged as follows:

RTD 3958' 8 5/8 csg set at 298' cwc Gmt. Mat 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 450' and displaced 50 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/13/71  
INV. NO. 3544-11

Signed: Geo E. Murrain  
Well Plugging Supervisor