

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-21834-00-00  
Spot: NWSENW Sec/Twnshp/Rge: 35-26S-12W  
3684 feet from S Section Line, 3690 feet from E Section Line  
Lease Name: MARDIS E Well #: 1-35  
County: PRATT Total Vertical Depth: 4382 feet

Operator License No.: 31000  
Op Name: PRATER OIL & GAS OPERATIONS, INC.  
Address: 1303 N MAIN STREET  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4070		WITH 2 SX CMT
PROD	4.5	4363	1978	WITH 175 SX CMT
SURF	8.625	350		WITH 230 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/04/2017 8:30 AM  
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC  
Proposal Revd. from: RON PRATER Company: PRATER OIL & GAS Phone: (620) 770-0856

Proposed Plugging Method: SET CIBP @ 4070' WITH 2 SX CMT. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/05/2017 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4070' & PUT 2 SX CMT ON TOP OF CIBP THOROUGH DUMP BAILER. 1ST PLUG AT 725' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 389' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 50 SX CMT. LAID TBG DOWN. TOP HOLE OFF WITH ANOTHER 50 SX CMT. WELL ON VACUUM. SHUT DOWN TO LET CMT SET. 1/5/17: TAGGED TOC @ 160'. WAIT ON CMT. TOPPED OFF WELL WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4120	4150		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN) INVOICED

RECEIVED  
JAN - 6 2017  
KCC DODGE CITY

JA

JAN 19 2017 Form CP-2/3