

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-20683-00-00  
Spot: S2SWSE Sec/Twnshp/Rge: 21-33S-6W  
330 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: HARRISON Well #: 1  
County: HARPER Total Vertical Depth: 4532 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD   | 4.5  | 4529       | 1121        | 300 SX   |
| SURF   | 8.63 | 251        |             | 200 SX   |

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/07/2016 12:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (405) 635-5287

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/08/2016 6:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP @ 4421' CIRCULATED CASING WITH MUD & 10 SKS CEMENT. PULLED 1121' CASING . RUN IN HOLE WITH TUBING & SPOTTED 35 SX CEMENT AT 1000'. PULLED TUBING TO 700' & SPOTTED 35 SX CEMENT. PULLED TUBING TO 300' & CIRCULATE CEMENT TO SURFACE WITH 85 SKS CEMENT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4471 | 4478 |      |          |

Remarks: CLASS C CEMENT. ORR ENTERPRISES

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

JAN 19 2017

Form CP-2/3