

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21442-00-00
Spot: SWSENE Sec/Twnshp/Rge: 4-34S-6W
2310 feet from N Section Line, 990 feet from E Section Line
Lease Name: CLARK Well #: 1-4
County: HARPER Total Vertical Depth: 4590 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4590	1236	150 SX
SURF	8.63	267		225 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/26/2016 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES Phone: (405) 635-5287

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 10/28/2016 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4455', THE CASING WAS LOADED WITH MUD & 10 SKS OF CEMENT WAS SPOTTED ON THE PLUG. THE CASING WAS RECOVERED FROM 1236' & PULLED FROM WELLBORE. TUBING WAS RUN TO 1050', WHERE 35 SX OF CEMENT WAS SPOTTED. PULL TUBING TO 700' & SPOTTED 35 SX CEMENT. PULLED TUBING TO 315' & CIRCULATE CEMENT TO 0' WITH 90 SX OF CEMENT.

Perfs:


Top	Bot	Thru	Comments
4505	4515		

Remarks: ORR ENTERPRISES

Plugged through: TBG

District: 02

Signed _____



(TECHNICIAN)

INVOICED
JAN 19 2017

Form CP-2/3