

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-20654-00-00
Spot: NENESE Sec/Twnshp/Rge: 8-12S-15W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: OSWALD CC Well #: 9
County: RUSSELL Total Vertical Depth: 3249 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3249		275 SX
SURF	8.625	216		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/12/2016 9:30 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION DBA Phone: (785) 885-8240

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/800 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/12/2016 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

12/09/2016- Drilled out CIBP at 2440'. Hole in casing from 2300' - 2305'.
12/12/2016- Ran tubing to 3112' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2046' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 815' and pumped 75 sx cement w/200 # hulls. Cement circulated to pit. POOH. Topped off with 15 sx cement. Hooked to braden head and pumped 5 sx cement at 300 psi. Hole standing full.

GPS: 39.02247 -099.00301

Perfs:

Top	Bot	Thru	Comments
3152	3155		
3116	3122		
3096	3101		
3074	3080		
3024	3030		
2991	2995		
2980	2984		
2966	2974		
2455	2465		

KCC WICHITA
JAN 09 2017
RECEIVED

Remarks: BASIC CEMENTING TICKET # 14877 A

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

INVOICED

JAN 14 2017

Form CP-2/3

DEC 16 2016